BRUHAT BENGALURU MAHANAGARA PALIKE
EXECUTIVE ENGINEER (ELECRICALS) DASARAHALLI ZONE
SCHEDULE-B

Indent Number:BBMP/2021-22/EL/WORK_INDENT50077
Name of work: Annual Maintenance of street lights package D-1 in Kammagondanhalli Surrounding Area ward no 12

Issued to :M/s.CHIKKANNA G.(CHETHAN ELECTRICALS)

SNo	Item Name	Unit	Rates Quoted by Contractor		
			Estimate Quantity	In Figures (Rs.)	In Words (Rs.)
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. 36/40 W fluorescent tube light street lighting system.	Each	320	685.45	Rupees Six Hundred Eighty Five and Forty Five Paisa Only
2	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. 125W HPMV Park lighting system.	Nos	22	756.29	Rupees Seven Hundred Fifty Six and Twenty Nine Only
3	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed belowPoles with 250W HPSV street lighting system.	Each	1780	1019.41	Rupees One thousand Sixty and Eighty Paisa Only.
4	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below 400 watts HPSV street light /High mast lighting system.	Each	80	1118.08	Rupees One Thousand One Hundred Eighteen and Eight Paisa Only.
5	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing [illegible] etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 24 Watt to 40 Watt LED Park/ street lighting system.	Each	4	880.01	Rupees Eight Hundred and One Paisa Only

For CHETHAN ELECTRICALS

PROPRIETOR

EE (Elc)
DZ

Scanned by CamScanner

6	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 40 Watt to 65 W LED street Light lighting system.	Each	350	1147.43	Rupees One Thousand One Hundred Forty seven and Forty Three Only.
7	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 90W LED street light lighting system.	Each	90	1377.66	Rupees One Thousand Three Hundred Seventy Seven Only.
8	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for110/120 watt LED street light lighting system	Nos	1	1575.5	Rupees One Thousand Five Hundred Seventy Five and Five Only.
9	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 150/180 watt LED street light /High mast lighting system.	Nos	1	1871.51	Rupees One thousand Eight Hundred Seventy One abd Fifty One Only.
10	Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof, dust proof, water proof, corrosion proof having Internally Embedded gasket on both lid and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cutout with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility.300mmx450mmx214mm	Each	5	5127	Rupees Five Thousand One Hundred Twenty seven Only.
11	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947 100 to 125Amps	Each	10	7200	Rupees Seven Thousand Two Hundred Only.
12	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, Indicator ON/OFF, 4Amps cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.50-63 Amps SP	Each	20	723	Rupees Seven Hundred Twenty Three only.

For CHETHAN ELECTRICALS

PROPRIETOR

EE (Ele)
DZ

Scanned by CamScanner

...ting Microprocessor Based Astronomical ... with using necessary bolts, nuts and washers.	Each	19	4030	Rupees four Thousand Thirty Only.
...lighting/power circuit using one of FRLS PVC ... 1100V grade, multistrand copper wire with low ... resistance single core in open or concealed ... wiring with specified IS-694:confirming to latest ...dments 6 sqmm	Mtr	10	70	Rupees Seventy Only.
...plying tinned copper lugs and crimping and wiring to ...minal point for wire of the following sizes.6 sqmm	Each	100	7	Rupees Seven Only.

Executive Engineer (Ele)
...Zone.
Bruhat Bengaluru Mahanagara Palike.

EE (Ele)
DZ

For CHETHAN ELECTRICALS

PROPRIETOR

Scanned by CamScanner